		regry
COII	No	*24*

MVCT/MBCT/MVCP - 202

M.E./M.Tech., II Semester

Examination, June 2014

Prefabrication Design And Its Construction Tech.

Time: Three Hours

Maximum Marks: 70

- Note: i) Answer any five questions.
 - ii) All questions carry equal marks.
- Name different mass produced prefabricater of steel reinforced concrete, and masonry and describe one from each in details.
- 2. Describe following

.

- a) Limitations of precast construction in India.
- b) Modular coordination as per NBC of India.
- Standardization and its necessity.
- Describe plant layout, machines and mould used for precast roofing and wall elements.
- Describe lift points and explain design of a member with two and three lift points.
- Describe tolerances and deviations and their permissible values for precast components.

- 7. Describe following
 - i) V plate system
 - ii) Lift slab systems
- 8. Write short notes on following (any four)
 - ny four)

repvonline.com

14

14

- i) Modular grid
- ii) Failure of precast constructions
- iii) Horizontal transportations equipments
- iv) Vertical transportations equipments
- v) Planning and design module
